

2013 JOB LIST AND SCHEDULE

| ROAD NAME: | TYPE OF WORK: | BRIEF DESCRIPTION OF LOCATION | DIRT WORK | BASE WORK | DITCH WORK | PEEL EDGES | PATCH WORK | BRUSH CUT | TREES CUT | BUCKET TRUCK | CULVERT NEEDED | BRIDGE WORK | UTILITY WORK | FROM WHERE TO WHERE: | LENGTH: | SY | CHIP OIL QTY. 0.30 1st app., 0.40 2nd app | PRIME QTY. @ 0.20 | TACK QTY. @ 0.1 | NOTES: |
|------------|---------------|-------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------|--------------|----------------|-------------|--------------|----------------------|---------|----|---|-------------------|-----------------|--------|
|------------|---------------|-------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------|--------------|----------------|-------------|--------------|----------------------|---------|----|---|-------------------|-----------------|--------|

SOUTHEAST AREA

| | | | | | | | | | | | | | | | | | | | | |
|--------------------|---------|------------------------|---|---|---|---|---|---|--|---|---|--|--|--|------|--------|--|--|-------|------------------------|
| Frisco Springs Rd. | Asphalt | Off Erwin McGarrah | | | | | X | X | | | | | | Erwin McGarrah to end | 1.2 | 14,080 | | | 1,408 | |
| Ervin McGarrah | Asphalt | Off Hwy. 264 | | | | | | | | | | | | From Hwy. 264 North to end | 5.62 | 65,941 | | | 6,594 | |
| Primrose Rd. | Asphalt | Off Hwy. 264 | | | | | | | | | | | | From Hwy. 264 North to S. Primrose Rd. | 0.75 | 8,800 | | | 880 | |
| N. Primrose Rd | Asphalt | Off Hwy. 264 | | | | | | | | | | | | From Frisco Cemetery Rd South to S Primrose Rd | 0.74 | 8,683 | | | 868 | |
| S. Primrose Rd. | Asphalt | Off Hwy. 264 | | | | | | | | | | | | From Hatcher Rd. North to N. Primrose Rd | 1.0 | 11,733 | | | 1,173 | |
| McCann | Asphalt | Off So. Old Wire | X | X | X | | | X | | X | X | | | End of asphalt to S J St | 0.1 | 1,173 | | | 117 | |
| Blue Hill Rd. | Asphalt | Off Hwy. 94/ Monte Ne | | | X | | | | | X | | | | Hwy. 94 up hill to city limit | 0.8 | 9,387 | | | 939 | |
| Grimes Dr. | Asphalt | Prairie Creek | | | | X | X | | | | | | | From Hwy. 12 to end | 1.0 | 11,733 | | | 1,173 | Dirt around guardrails |
| Grimes Dr W | Asphalt | Prairie Creek | | | | | | | | | | | | Circle off of Grimes Dr | 0.5 | 5,867 | | | 587 | |
| Linville Road | Asphalt | East of Prairie Creek | | | | X | X | | | | X | | | From Hwy. 12 to Pleasant Ridge | 0.95 | 11,147 | | | 1,115 | |
| Pleasant Ridge Rd. | Asphalt | Close to Beaver Shores | | | X | X | X | | | | | | | Asphalt West to City limit | 1.0 | 11,733 | | | 1,173 | |
| Elm Ln. | Asphalt | Beaver Shores | | | | | | | | | | | | Cypress Lane South to Willow Dr | 0.4 | 4,693 | | | 469 | |
| Rainbow Dr. | Asphalt | Beaver Shores | | | | | | | | | | | | Elm Lane to Willow Dr | 0.3 | 3,520 | | | 352 | |

2013 JOB LIST AND SCHEDULE

| ROAD NAME: | TYPE OF WORK: | BRIEF DESCRIPTION OF LOCATION | DIRT WORK | BASE WORK | DITCH WORK | PEEL EDGES | PATCH WORK | BRUSH CUT | TREES CUT | BUCKET TRUCK | CULVERT NEEDED | BRIDGE WORK | UTILITY WORK | FROM WHERE TO WHERE: | LENGTH: | SY | CHIP OIL QTY. 0.30 1st app., 0.40 2nd app | PRIME QTY. @ 0.20 | TACK QTY. @ 0.1 | NOTES: |
|-------------------|---------------|-------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------|--------------|----------------|-------------|--------------|----------------------------|---------|--------|---|-------------------|-----------------|--|
| Cavern Drive | Asphalt | 2 Miles E of War Eagle Rd | | | X | | X | | | | X | | | From Hwy. 12 to end | 0.57 | 6,688 | | | 669 | Can't find end of culvert at address 21494 |
| Rambo Rd. | Asphalt | 2 Miles E of War Eagle Rd | | | | | | | | | | | | | 2.3 | 26,400 | | | 2,640 | |
| Rambo North Rd | Asphalt | 2 Miles E of War Eagle Rd | | | | | | | | | | | | | 0.2 | 2,347 | | | 235 | |
| John's Hill Rd 2 | Single chip | Off Schoolhouse | | | | | X | | | | | | | | 0.3 | 3,520 | 1,056 | | | |
| Schoolhouse Dr. 2 | Double chip | Off Cow Face | X | | | | | | | | | | X | From Cow Face North to end | 1.1 | 12,907 | 9,035 | 2,581 | | |
| Cloverdale 1 | Double chip | Close to Rogers Airport | DONE | X | | | | | DONE | | | | | End of asphalt to end | 0.8 | 9,387 | 6,571 | 1,877 | | |

NORTHEAST AREA

| | | | | | | | | | | | | | | | | | | | | |
|-------------------|---------|---------------------------------|--|--|---|---|---|--|---|---|--|--|--|---|------|--------|--|--|-------|---------------------|
| W. McNelly Rd | Asphalt | (Benton Co. 40) | | | X | | X | | X | X | | | | From Hwy. 71 East to E. McNelly Rd | 1.0 | 11,733 | | | 1,173 | Share w/Bentonville |
| E. McNelly Rd | Asphalt | Off W. McNelly Rd | | | | | | | | | | | | From W. McNelly Rd. East to Hwy. 94 | 4.30 | 50,453 | | | | |
| Kreeger Ln. | Asphalt | Hwy. 94/ Brush Creek | | | | | | | | | | | | | 0.2 | 2,347 | | | 235 | Narrow bridge |
| Cemetery Rd. | Asphalt | Off Hwy. 62 past Rogers airport | | | | | | | | | | | | Hwy. 62 E. North to E. Tucks Chapel Rd. | 0.89 | 10,443 | | | 1,044 | |
| Holiday Hills Dr. | Asphalt | Off Posey Mtn | | | X | | | | | X | | | | Posey Mountain Turnoff South to end | 0.9 | 10,560 | | | 1,056 | |
| Jim's Trail | Asphalt | Off Posey Mtn | | | | X | | | | X | | | | Holiday Hills Dr South to end | 0.7 | 8,213 | | | 821 | |

2013 JOB LIST AND SCHEDULE

| ROAD NAME: | TYPE OF WORK: | BRIEF DESCRIPTION OF LOCATION | DIRT WORK | BASE WORK | DITCH WORK | PEEL EDGES | PATCH WORK | BRUSH CUT | TREES CUT | BUCKET TRUCK | CULVERT NEEDED | BRIDGE WORK | UTILITY WORK | FROM WHERE TO WHERE: | LENGTH: | SY | CHIP OIL QTY. 0.30 1st app., 0.40 2nd app | PRIME QTY. @ 0.20 | TACK QTY. @ 0.1 | NOTES: |
|----------------------|---------------|-----------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------------------------------|--------------|----------------|-------------|--------------------------|---|---------|--------|---|-------------------|--------------------|-------------------------|
| Posey Mtn Turnoff | Asphalt | Off Posey Mtn | | | X | | | | | | | | | Posey Mountain Dr South to Holiday Hills Dr | 1.3 | 15,253 | | | 1,525 | |
| Cemetery Rd. | Asphalt | For City of Gateway-North on 37 | | X | | | | | | | | | | E. Tucks Chapel Rd. South to Hwy. 62 | | - | | | - | |
| Dogwood Dr. | Asphalt | In Lost Bridge | | | | | | | | | X | | | From recent asphalt to E. Airport Drive | 1.3 | 15,253 | | | 1,525 | |
| Indian Bow Circle | Asphalt | Off of Schaffer | | | | | | | | | | | | Shaffer Rd. South to end | 0.5 | 5,867 | | | 587 | Too narrow to chip |
| Arrow Lane | Asphalt | Off of Schaffer | | | | | | | 13475 address for a culvert issue | | | | Indian Bow Circle to end | 0.3 | 3,520 | | | 352 | Too narrow to chip | |
| Timberline Dr | Single chip | On way to Lost Bridge | | | | | | | | | | | | Off of Lodge Drive (makes a loop) | 0.5 | 5,867 | 1,760 | | | |
| Lodge Dr. | Single chip | On way to Lost Bridge | | | | | | | | | | | | Hwy. 127 South to Slate Gap | 0.1 | 1,173 | 352 | | | |
| Shaffer Rd | Single chip | On way to Lost Bridge | X | | X | | | | | | | | | Hwy. 127 to end | 2.0 | 23,467 | 7,040 | | | Taking off sharp corner |
| Indian Creek Dr | Single chip | On way to Lost Bridge | | | X | X | X | | | | | | | Shaffer Rd to end | 0.7 | 8,213 | 2,464 | | | |
| Indian Creek Place | Single chip | On way to Lost Bridge | | | X | | | | | | | | | Indian Creek Dr to Vista Shores Dr | 0.1 | 1,173 | 352 | | | |
| Lowland Way | Single chip | Past Lost Bridge, end of Hwy. 127 | | | X | X | X | | | | | | | Loch Mor In to end | 0.1 | 1,173 | 352 | | | |
| Patton Rd. 6 | Double chip | Off of Hwy. 72 E of Pea Ridge | X | X | X | | | | X | X | X | | X | From Hwy. 72 North to first curve | 1.3 | 15,253 | 10,677 | 3,051 | | |
| Dogwood Valley Rd. 5 | Double chip | Off Posey Mtn | X | X | X | | | | | X | | | | Posey Mountain Turnoff to end | 1.5 | 17,600 | 12,320 | 3,520 | | |

2013 JOB LIST AND SCHEDULE

| ROAD NAME: | TYPE OF WORK: | BRIEF DESCRIPTION OF LOCATION | DIRT WORK | BASE WORK | DITCH WORK | PEEL EDGES | PATCH WORK | BRUSH CUT | TREES CUT | BUCKET TRUCK | CULVERT NEEDED | BRIDGE WORK | UTILITY WORK | FROM WHERE TO WHERE: | LENGTH: | SY | CHIP OIL QTY. 0.30 1st app., 0.40 2nd app | PRIME QTY. @ 0.20 | TACK QTY. @ 0.1 | NOTES: |
|--------------------------------|---------------|-----------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------|--------------|----------------|-------------|---------------|---|---------|--------|---|-------------------|-----------------|-------------------|
| NORTHWEST AREA | | | | | | | | | | | | | | | | | | | | |
| Stateline Rd | Single chip | Off 59 N of Sulphur Springs | | | X | X | | | | | | | | Heston Rd East to Hwy. 59 | 4.1 | 48,107 | 14,432 | | | |
| Beatty Rd. | Single chip | Off Stateline | | | | | | | | | | | | Stateline South to Hwy. 72 | 4.3 | 50,453 | 15,136 | | | |
| Sibley Rd. | Single chip | Off Beatty | | | X | X | | | | X | | | look at boxes | Stateline South to Roundtop Rd. | 0.6 | 7,040 | 2,112 | | | |
| Stagecoach Rd | Single chip | Off Beatty | | | X | | X | | | X | | | look at | From Mt. Olive to Hwy. 72 | 4.0 | 46,933 | 14,080 | | | |
| Bredehoeft Rd.(finish crown) 4 | Double chip | N. of Y City | | | | | | | | | | | | From Y City North to existing chip and seal | 0.5 | 5,867 | 4,107 | 1,173 | | |
| N. Tilly's Hill (more rock) 3 | Double chip | Off Hwy. 102 towards Decatur | | X | | | | | | | | | | Hwy. 102 South to S. Tillys Hill | 0.3 | 3,520 | 2,464 | 704 | | Base finish/crown |
| S. Tilly's Hill (more rock) 3 | Double chip | Off Hwy. 102 towards Decatur | | X | | | | | | | | | | N. Tillys Hill South to Y City | 1.0 | 11,733 | 8,213 | 2,347 | | Base finish/crown |
| Oak Hills Dr | Single chip | Off Punkin Hollow | | | X | | | | | X | | | | Off Peach Orchard, makes a loop | 1.3 | 15,253 | | | | |
| Roundtop Dr. | Asphalt | West of Hwy. 59 Sulphur Spgs | | | | | | | | | | | | From Hwy. 59 West to Sibley Rd. | 1.56 | 18,304 | | | 1,830 | |
| Roundtop Rd | Asphalt | West of Hwy. 59 Sulphur Spgs | | | | | | | | | | | | From Roundtop Dr South to Spring St | 0.32 | 3,755 | | | 375 | |
| Murdock Rd | Asphalt | From Philpot to Phillips Cemetery | | | | | | | | | | | | 22', light cracking, | 0.5 | 5,867 | | | 587 | |
| Hendrix | Asphalt | | | | | | | | | | | | | | | - | | | - | |
| Chicken Rd | Asphalt | | | | | | | | | | | | | From Limekill East to Mt. Olive | 1.2 | 14,080 | | | 1,408 | |
| Fruitwood Rd. | Asphalt | | | | | | | | | | | | | paved section | 1.3 | 15,253 | | | 1,525 | |

2013 JOB LIST AND SCHEDULE

| ROAD NAME: | TYPE OF WORK: | BRIEF DESCRIPTION OF LOCATION | DIRT WORK | BASE WORK | DITCH WORK | PEEL EDGES | PATCH WORK | BRUSH CUT | TREES CUT | BUCKET TRUCK | CULVERT NEEDED | BRIDGE WORK | UTILITY WORK | FROM WHERE TO WHERE: | LENGTH: | SY | CHIP OIL QTY. 0.30 1st app., 0.40 2nd app | PRIME QTY. @ 0.20 | TACK QTY. @ 0.1 | NOTES: |
|--------------|---------------|-------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------|--------------|----------------|-------------|--------------|--------------------------------------|---------|-------|---|-------------------|-----------------|--------|
| Mt. Olive Rd | Asphalt | | | | | | | | | | | | | From city limits North to Chicken Dr | 0.4 | 4,693 | | | 469 | |

SOUTHWEST AREA

| | | | | | | | | | | | | | | | | | | | | |
|-----------------------------|-------------|---------------------------------|---|---|---|--|---|---|--|---|---|--|---|-------------------------------------|------|--------|--------|--|-------|------------------------------|
| Aubrey Long Rd. (At Bridge) | Asphalt | For City of Springtown | | | | | | | | | | | | At bridge, see map | | - | | | - | Talk to City about prep work |
| Bozarth Cemetery | Asphalt | Off WPA | | | | | | | | | | | | WPA West to dirt | 0.6 | 7,040 | | | 704 | |
| Villa View | Asphalt | Off Hwy. 43 N. of Siloam | | | | | | X | | X | | | | County portion of road, see map | 0.2 | 2,347 | | | 235 | Talk to Siloam Springs |
| Sycamore Heights | Asphalt | Off Hwy. 43 N. of Siloam | | | | | | | | | | | | Hwy. 59 West | 0.32 | 3,755 | | | 375 | Talk to Siloam Springs |
| Sunset Drive | Asphalt | Off Off 71B towards Bella Vista | | | | | | | | | | | | Hwy. West to Cunningham | 0.49 | 5,749 | | | 575 | |
| Windmill Rd. | Asphalt | Off Hwy. 112 | X | X | X | | | | | | X | | X | From Hwy. 112 W. to Morning Star | 1.1 | 12,907 | | | 1,291 | |
| Bethlehem Rd. | Asphalt | Off Hwy. 102 | | X | | | | | | | | | | From Hwy. 102 W to Burgin Valley | 1.4 | 16,427 | | | 1,643 | |
| WPA | Single chip | N of 112, W of Gentry | | | | | X | | | | | | | Falling Springs So to Hwy. 112 | 4.8 | 56,320 | 16,896 | | | |
| Gum Springs Rd | Single chip | S off 412, E of Siloam | | | | | | | | | | | | Hwy. 412 to Keck Rd | 0.2 | 2,347 | 704 | | | |
| Keck Rd | Single chip | S off 412, E of Siloam | | | | | X | | | | | | | From E. Kenwood Dr East to dirt | 1.3 | 15,253 | 4,576 | | | |
| E. Kenwood | Single chip | S off 412, E of Siloam | | | | | X | | | | | | | From Keck North to Bruce Rutherford | 0.2 | 2,347 | 704 | | | |
| Bill Young Rd | Single chip | Off 59, before Siloam | | | | | X | | | | | | | 59 East to Fairmount | 2.7 | 31,680 | 9,504 | | | |

2013 JOB LIST AND SCHEDULE

| ROAD NAME: | TYPE OF WORK: | BRIEF DESCRIPTION OF LOCATION | DIRT WORK | BASE WORK | DITCH WORK | PEEL EDGES | PATCH WORK | BRUSH CUT | TREES CUT | BUCKET TRUCK | CULVERT NEEDED | BRIDGE WORK | UTILITY WORK | FROM WHERE TO WHERE: | LENGTH: | SY | CHIP OIL QTY. 0.30 1st app., 0.40 2nd app | PRIME QTY. @ 0.20 | TACK QTY. @ 0.1 | NOTES: |
|-----------------------------|---------------|-----------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------|--------------|----------------|-------------|--------------|--|---------|--------|---|-------------------|-----------------|--------|
| Meadow Wood Dr. | Single chip | Off 59 South of Siloam | | | | X | X | | | | | | | Hwy. 59 to end | 0.9 | 10,560 | 3,168 | | | |
| Crestwood | Single chip | Off Meadow Wood Dr | | | | X | | | | | | | | Off Meadow Wood, 1st on left | 0.1 | 1,173 | 352 | | | |
| Ridgeway Ln. | Single chip | Off Meadow Wood Dr | | | | X | | | | | | | | Off Meadow Wood, 1st on right | 0.1 | 1,173 | 352 | | | |
| Ridgeway Dr. | Single chip | Off Meadow Wood Dr | | | | X | | | | | | | | Off Meadow Wood, last on right | 0.5 | 5,867 | 1,760 | | | |
| Hico Rd | Single chip | W of Gentry off Country Club | | | | | X | | | | | | | From Dawn Hill So to City limits | 0.8 | 9,387 | 2,816 | | | |
| Kincheloe (chip 2014) | Double chip | Off 412 E of Siloam | X | X | X | | | X | | X | | | X | From Hwy. 412 to Chamber springs | | 14,080 | | | | |
| Chamber Springs (chip 2014) | Double chip | Off 412 E of Siloam | X | X | | | | X | | X | X | | X | From Kincheloe South to Hwy. 16 | | 59,840 | | | | |
| Carlton Dr | | South of Hwy. 102, West of Gentry | | | | | | | | | | | | From Falling Springs Rd West to Coon Hollow Rd | 0.91 | 10,677 | | | 1,068 | |
| Philips | | | | | | | | | | | | | | From Cemetery West to Mill Dam | 0.9 | 10,560 | | | 1,056 | |
| Keck Rd | | South end which is West to dirt | | | | | | | | | | | | | 1.3 | 15,253 | | | 1,525 | |
| Gum Springs Rd | | | | | | | | | | | | | | Hwy 412 South East to Keck Rd | 0.2 | 2,347 | | | 235 | |
| Ruby Hall | | | | | | | | | | | | | | | | - | | | - | |
| N. Pleasant Valley | | | | | | | | | | | | | | Hwy. 59 South to Vaughn Rd | 1.8 | 21,120 | | | 2,112 | |

2013 JOB LIST AND SCHEDULE

| ROAD NAME: | TYPE OF WORK: | BRIEF DESCRIPTION OF LOCATION | DIRT WORK | BASE WORK | DITCH WORK | PEEL EDGES | PATCH WORK | BRUSH CUT | TREES CUT | BUCKET TRUCK | CULVERT NEEDED | BRIDGE WORK | UTILITY WORK | FROM WHERE TO WHERE: | LENGTH: | SY | CHIP OIL QTY. 0.30 1st app., 0.40 2nd app | PRIME QTY. @ 0.20 | TACK QTY. @ 0.1 | NOTES: |
|---------------------|---------------|-------------------------------|-----------|-----------|------------|------------|------------|-----------|-----------|--------------|----------------|-------------|--------------|---|---------|--------|---|-------------------|-----------------|--------|
| Taylor Orchard Lane | | Siloam City lake to Dawn Hill | | | | | | | | | | | | From S. Marion Lee Rd Southwest to Dawn Hill Rd.??? | 1.8 | 21,120 | | | 2,112 | |

TOTALS:

| |
|--------------|
| 81.27 |
| MILES |

| | | |
|----------------|---------------|---------------|
| 153,355 | 15,253 | 47,837 |
| CHIP OIL | PRIME | TACK |

| | | |
|------------------------|------------------------|--------------------------|
| \$ 1,700,000.00 | \$ 1,490,750.00 | \$ 655,916.67 |
| ORIGINAL BUDGET | 1/2 CENT TAX FOR ROADS | 1/2 CENT TAX FOR BRIDGES |

TOTAL FOR 1/2 CENT TAX = \$2,146,666.67